



**Shyama Prasad Mukherji College
University of Delhi**

Quotation

For

Repair of Auditorium Terrace

SHYAMA PRASAD MUKHERJI COLLEGE
University of Delhi
Punjabi Bagh (West), New Delhi – 110026
Ph : 25224499, email : spmcollegedu@gmail.com, website : http:spm.du.ac.in

Ref No. : *SPMG/2019-352*

Date : *3-9-2019*

NOTICE INVITING QUOTATION

Sealed item rate quotations are hereby invited for the following work, so as to reach the office of the undersigned upto 1:00 p.m. on 23.09.2019.

1. Description of work : Repair of Auditorium Terrace
2. Site of work : SPM College
3. Scope of work : Repair work
4. Owner Address : Shyama Prasad Mukherji College
Punjabi Bagh (West), Delhi - 110026
5. Details of Quotation
 - a. Estimated cost of work : Rs. 2,31,000/-
 - b. Time of Completion : 40 days
 - c. Date of start of quotation : 03-09-2019
 - d. Last date and time of submission : 23-09-2019 at 1:00 p.m.
of quotation
 - e. Earnest Money Deposit : Rs. 5000/-
(E.M.D) Deposit only in the form of Bank draft

The documents can be seen and obtained from the college website <http://spm.du.ac.in> on or before 23-09-2019.

Pupk
3.09.19.

Principal (Officiating)
Shyama Prasad Mukherji College

Terms and Conditions:-

1. The Contractor shall quote rates with GST, No extra GST shall be paid to the Contractor.
2. 10% of the bill will be deducted by the college on each running bill and shall be retained as Security Deposit. The amount so deducted shall be returned after the Defect Liability Period of six months. The DLP will be counted from the date of completion of work and handing over to the college.
3. 1% of the bill will be deducted towards water and electricity charges from each running account bill.
4. Compensation for delay of work @1.5% per month of delay to be computed on per day basis and levied on the contractor on delay of work.
5. Labour laws are to be complied by the contractor. The contractor shall obtain a valid license under the Contract Labour (R&A) Act 1970 and the contract labour (Regulation and Abolition) Central Rules 1971 before the commencement of work and continue to have a valid license until the completion of work. The contractor shall also abide by the provisions of the Child Labour Act 1986.
6. Interested Contractors, Firms, Companies are advised to submit the quotation and EMD. No exemption shall be given to anybody by any way.
7. The contractors / firms are advised to inspect the site, examine the drawings and make all investigations regarding the extent of work, its scope and conditions under which the work is to be executed. No claim for any extra payments of any kind on account of lack of information about the site conditions shall be entertained.
8. The rates shall be quoted both in figures and words
9. The contractor / firm may be required to produce documents regarding partnership and / or Articles of Association of the Company along with the tender document.
10. Earnest money deposited by the Contractor / firm shall be liable to be forfeited in case the Contractor / firm does not commence the work within 7 (seven) days of the date of issue of work order.
11. The offer shall remain open for a period of 60 days from the stipulated date of submission of quotation.
12. The Owner reserves the right to reject any or all of the quotations, either in whole or in part, without assigning any reason for so doing.
13. Earnest money deposited by the contractors / firms shall be returned after 30 days of the date of award of work to the successful tenderer. This deposit shall not bear any interest.

*Subh
3.05.19.*

Principal,
SHYAMA PRASAD MUKHERJI COLLEGE
UNIVERSITY OF DELHI, DELHI

BILLS OF QUANTITY

Name of work : **Repair of Auditorium Terrace**

S.No	Items	Qty	Unit	Rate	Amount
1	Demolishing mud phaska in terracing and disposal of material within 50 metres lead.	6	cum		
2	Demolishing brick tile covering in terracing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	57	sqmtr		
3	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	70	sqmtr		
4	14.13 Regrading terracing of mud phaska covered with tiles or brick, in cement by dismantling tiles or bricks, removing mud plaster, preparing the surface of mud phaska to proper slope, relaying mud plaster gobi leaping and tiles or bricks, grouted in cement mortar 1:3 (1 cement : 3 fine sand), including replacing unserviceable tiles or bricks with new ones and disposal of unserviceable material to the dumping ground (the cost of the new tiles or brick excluded), all complete as per directions of Engineer-In-Charge.	57	sqmtr		
5	13.2; 15 mm cement plaster: 13.2.1 1:4 (1 cement : 4 fine sand) 100	70	sqmtr		
6	13.44 Finishing walls with water proofing cement paint of required shade : 13.44.1 New work (Two or more coats applied @ 3.84 kg/10 sqm)	100	sqmtr		
7	13.31 Pointing on brick work or brick flooring with cement mortar 1:3 (1 cement : 3 fine sand): 13.31.1 Flush / Ruled/ Struck or weathered pointing	30	sqmtr		
8	6.4 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.2 Cement mortar 1:6 (1 cement : 6 coarse sand)	6	cum		
9	10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	780	kg		

10	5.22A Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level 5.22A.6 Thermo-Mechanically Treated bars of grade Fe-500 D or more.	100	kg		
11	Repair of terrace with micro concrete 20mm thick layer of micro concrete. Ist step cleaning the surface / washing the surface and laying of micro concrete.	1.15	cum		
12	Supply of new brick tiles used as per direction of Engineer-in-charge	1800	nos		
	Total				

(In Words) Rs. _____.

Signature _____

Name and Address _____

of the Firm / Contractor _____

Company Seal _____